







Forward

Thank you for choosing the HISAKA plate heat exchanger.

The HISAKA plate heat exchanger is a relatively trouble free, high performance equipment, but proper maintenance will further increase its reliability, and extend its life.

This booklet is a compilation of knowledge gathered over the years at HISAKA, as the sole domestic plate type heat exchanger manufacturer in Japan. Please utilize the booklet to avoid troubles and to improve productivity of the plate heat exchanger.

> HISAKA WORKS, LTD. Heat Exchanger Div. Japan

1—Construction of Plate Heat Exchanger	
Mechanism	
2—Maintenance for Equipment	
Performance	•7
3—Maintenance	•8
Spare parts	•8
Deterioration of gaskets	●12
Cleaning methods	●14
4— Introduction of Maintenance Services	●16
"Full Service Package"	●16
Other services	●17
5— Fault Detection	●18
5-1 Scaling	●18
Langelier saturation index and scaling	●18
Marine growth	●20
Seawater strainer	•22
5-2 Corrosion of Plate	●24
General corrosion	●24
Pitting corrosion	●25
Crevice corrosion	●27
Erosion corrosion	●29
Stress corrosion cracking	•30
5-3 Other Fault Detections	•32
Fatigue crack	•32
Plate deformation	•33
6— Overhauling	●34
7— To Extend the Lifetime of Your Heat	
Exchanger	●35

1— Construction of Plate Heat Exchanger Mechanism

Ever since its debut as a product in 1953, HISAKA plate heat exchanger has been highly reputed for its "high performance", "lightweight, compact design", "energy saving" and "easy maintenance characteristics", and have been widely applied in a variety of industries including chemical, HVAC (heating, ventilation, air conditioning), food, power station, shipbuilding, steel, mining, semiconductors and for environmental applications.


Construction

The heat transfer plate, is manufactured by press forming thin sheets of corrosionresistant metals such as stainless steel and titanium. A plate element consists of this heat transfer plate with its peripheral area sealed with a synthetic rubber gasket. In the plate heat exchanger, the required number of plate elements are suspended on a guide bar, and

precisely designed so that they work maximum performance in each process.

The heat transfer plate and gasket are high precision formed products, and tightened with uniform force in order to achieve high sealing performance.

Guide bar support





Tightening lengths

The dimension between the fixed and movable frame is called the tightening dimension, and the unit is tightened between the maximum dimension and the minimum dimension. The tightening lengths is shown on the assembly drawings and on the nameplate of the unit.

Manufacturing number

When contacting us in regards to maintenance, please notify us of the manufacturing number. It is possible to understand all specification of the unit, just with the manufacturing number. The manufacturing number is shown on the drawings and on the nameplate on the unit.






2— Maintenance for Equipment


There are no moving parts on a plate heat exchanger, making it a device with a low number of component parts, and relatively free of malfunctions or other trouble. However, with extended periods of operation, there may be deterioration of gaskets, scaling by water residue and other debris, and corrosion and cracking may occur. If left as is, this will lead to a reduction in performance, intermixing of fluids and leakages, and can ultimately lead to stopping of the unit and the entire plant. In order to prevent this, it is necessary to periodically disassemble the unit, and perform inspection and cleaning.








Cracking visual inspection (top) Cracking detection by dye penetration test (bottom)



Heat exchanger left alone without changing the gasket (top), crevice corrosion occurring at the gasket line (bottom)



Main reasons for reduction in performance and leakages of the plate heat exchanger, include the scaling by water inside the heat exchanger and deterioration of the gasket due to extended use. For the problem with scaling by water residue, we recommend that decreasing the performance be monitored, and to perform periodic opening and cleaning accordingly.




Scale accumulated on the plate surface

Performance

When the heat exchanger is used for extended lengths of time, scale will adhere inside, and the overall heat transfer coefficient will down over time. The initial performance is restored by periodically opening and cleaning the unit.



1 Hard scale inside the plates



3— Maintenance

The maintenance of the plate heat exchanger is largely divided into spare parts and plate cleaning. Spare parts consist of gaskets, plates, and frames, and methods of plate cleaning include mechanical cleaning and chemical cleaning.

Spare parts <Gasket>


The reliability of the gaskets has been proven through years of research, experience, evaluation and actual performance at HISAKA. Though a plate gasket seems simple, there are many technical ideas in the shape, thickness, width, material, and are nothing like the ordinary piping flange gaskets punched out from a rubber sheet material.

The selection of the synthetic rubber compound that is provided as the product, is closely evaluated for its cost, chemical resistance, heat resistance, and anti cracking performance. From several thousand compounds, we select those that clear these evaluation factors at the highest level. In addition, they are repeatedly checked in various endurance tests before the final decision, and are vulcanized and mold formed in precision dies that take into account amount of shrinkage for the final dimensions.

The gaskets are the only consumable part in the maintenance of plate heat exchangers. A lot number is shown on the gasket, making it possible to identify the date of manufacture, the die used, and material. For the material, color marking is utilized to make it easy to identify visually.



T With the lot number and yellow marking, it can be confirmed that this material is NBR.



↑ Gaskets are manufactured based on precision design.

Gasket material symbols and list of colors

Material				
Abbreviation	Symbol	Color marking	Product name	
NBR	Н	Yellow, 1 point	Nitrile-butadience rubber	
G-NBR	NBR	Yellow, 1 point		
	NBR	Yellow, 2 points		
	NBR	Yellow 1, Green 1		
NBR for Food	HF	Pink, 1 point	Food approved NBR	
	NBR	Yellow, 2 points		
EPDM	NE	Pink, 2 point	Ethylene-propylene Diene-Methylene Linkage	
	YE	Pink, 2 point		
	E	Pink, 2 point		
	EE	Pink, 2 point		
	E	Green, 1 point		
G-EPDM	EPDM	Pink, 2 points		
	E	Pink, 2 points		
EPDM for Food	NE	Pink, 2 points	Food approved EPDM	
	EPDM	Pink, 2 points		
R-EPDM	ER	Green, 2 points	High temperature EPDM	
IIR	V	Blue, 1 point	Chloro-isobuthene-isoprene rubber	
G-IIR	IIR	Red, 2 points	Butyl (isobuthene-isoprene)rubber	
N-IIR	Т	Brown, 1 point		
FPM	FV	N. A.	Fluorinated rubber	
R-FPM	RV	White, 1 point		
G-FPM	FPM	Purple, 1 point		
	FPM	Purple 1, White 1		
	FPM	Purple, 4 points		
Si	SS	N. A.	Silicone rubber	

The symbols and colors are current as of April 2005. For those that do not appear on this list, please contact us.

Guideline for regasketing

Operating temperature	Guideline for regasketing
$100^{\circ}C \leq$	1-3 years
$30^{\circ}C \le and 100^{\circ}C$	5-7 years
$\leq 30^{\circ}C$	within 7-10 years

As an additional condition, if there are applicable laws and regulations such as for Japanese Pressure Vessel Class 1 and high pressure gas safety laws, perform disassembly and inspection according to the applicable legislation or regulation. Refer to the separate page for regasketting. Make overall considerations including the corrosion resistance of the gasket for the fluid as well, and set a regasketing period.

3— Maintenance

<Plate>


The heat transfer plate is formed in the press facilities of HISAKA which have the largest 40,000 ton press machine in the world and other unique press machine. In order to press the plates under optimal conditions, the plate die is checked every few thousand to 10 thousand shots.

The plates in the plate heat exchanger are thin and of 0.5mm to 1.0mm in thickness. In order to press these thin plates without press defects such as flaw, necking, the high pressing tools design and manufacturing technology, and pressing technology of HISAKA are absolutely essential.

These plates are printed with a lot number using an electronic marker as well as gaskets, and the plate thickness, material, and manufacturing date can be found, and makes it possible to track down the mill certificate plate material by mill certificate.




Lot number Indicates that model LX-026, S316 is made of SUS316.





<Frame>

The frame plate is a pressure retaining part that maintains the sealing of the unit by tightening together the plates with uniform tightening force. Because of this, if there is corrosion or deformation, it will require periodic overhaul. There is also a model with rubber lined (NJ/NP type) on the connection holes of the frame plate to prevent the carbon steel material from corrosion by fluid. This rubber lined is called a rubber boot, and requires replacement if deterioration is found.



1 For a rubber boot type, a piping gasket is not necessary.



<Tightening bolts>

Tightening bolts and nuts will also begin to rust depending on the circumstance of the unit, so we recommend that periodic greasing be performed for rust prevention. Also, a bolt cover to protect the bolts, is available as an option.



<Other spare parts>

The plates and gaskets of the plate heat exchanger can be supplied, and tightening bolts, nuts, rubber boots, and adhesive glues can be also supplied for maintenance.



1 Maintenance parts

3— Maintenance

Deterioration of gaskets

Although high quality synthetic rubber is used for gaskets, deterioration due to aging is still unavoidable. Deterioration such as loss of elasticity, cracking or carbonization for rubber will decrease the sealing force, and will cause fluid leakage.




Deteriorated gasket

<Gasket life time>

It is known that the following relationship exists in plate gaskets.

(1) Compression ratio ε [%] and allowable operating pressure P [MPa]



 $P = \alpha \cdot \epsilon + \beta \cdots \cdot 1$

Here, a and b are constants regardless of plate type, and compression ratio ε [%] can be shown by equation (2).

$$\varepsilon[\%] = \frac{(t_0 - t)}{t_0} \times 100 \cdots 2$$

t₀: Compression free gasket thickness before operation [mm]

t : Gasket thickness when tightened [mm] When using this relationship, it is possible to predict the minimum compression free gasket thickness t_0 [mm] that will be required at the allowable operating pressure. ... (Fig. 1) In addition,


(2) Permanent compression set C/S [%] and time θ [h]

 $C/S = \gamma \bullet \theta^{\zeta} \dots \Im$

Here, γ and ζ are constants that are dependant on gasket material and temperature, and the permanent compression set is defined in equation (4).


$$C/S[\%] = \frac{(t_0-t_1)}{(t_0-t)} \times 100\cdots$$

t₁: Compression free gasket thickness after operation [mm]



From this relationship, it will be possible to predict the gasket thickness t_1 [mm] after a certain amount of time has passed. \cdots (Fig. 2)

Using this relationship, Fig. 3 shows the relationship between operating time and allowable operating pressure. When the permanent compression set of the gasket increases from operation start, and the allowable operating pressure goes down below the operating pressure, the initial leakage will occur. By retightening thereafter, the compression ratio of the gasket will be revived and it will be usable again, but when the permanent compression set increases further, the gasket will reach the limit of sealing and it will need to be replaced.



<Regasketing guideline>

Also, using the relationship of the previous section (1), it is possible to judge whether the gasket should be replaced by measuring the thickness of a gasket that has been used for a certain period of time. (Example of the judgment procedure)

<Observation>

There were no external defects on the

gasket such as bubbling, cracking, stickiness, melting or wrinkles, and there is no leakage from the unit.

Bending the gasket 180°, no cracks is on the gasket surface.

When measured gasket hardness, the result was 80°.


With the operating pressure of 0.5MPaG, when the gasket thickness was 3.1mm, and tightening is to be performed at the minimum gasket thickness of 2.6mm.

<Judgment>

Visual inspection … passed
Bending test … passed
Hardness … passed
Hardness is to be between 65° to 93°.
Operating pressure … passed
The allowable operating pressure is checked ε [%] from in equation (2) and Fig. 4.

$$\varepsilon = \frac{(3.1 - 2.6)}{3.1} \times 100 = 16.1\%$$

From Fig. 4, the allowable operating pressure 0.92 [MPa] > operating pressure 0.5 [MPa]. From $\textcircled{}\sim \textcircled{}$ here, this gasket is possible to use.



3— Maintenance

Cleaning methods


Remove the gasket from the plates, and clean with a deck brush, or water jet. In a case of water jet, to avoid deformation of the plate and damage to sealing surfaces, set on a flat panel and a reinforcement panel, and the water jet should be from a distance of 200mm or more.



1 Water jet



1 Brush cleaning



Allowable water jet pressures for plate

Plate	Plate	Max. water jet
thickness	material	pressure
mm		MPa
0.5	Titanium	3
0.6	Titanium	5
0.8	Titanium	10
1.0	Titanium	15
0.5	Stainless steel	5
0.6	Stainless steel	8
0.8	Stainless steel	15
1.0	Stainless steel	20




<Chemical cleaning>


Soaking...The plates are soaked in a chemical bath. In this case, it is necessary to control the process, being very careful of the chemical temperature, concentration and washing time so that the plates are not corroded by the chemicals.



Plates before cleaning



1 Soaking in a chemical bath to remove hard scale.



1 Plates after cleaning

Cleaning-in-place (CIP)...After washing through the heat exchanger by hot water with a higher flow rate than designed, a chemical (acid, alkali) is circulated for chemical cleaning. After chemical cleaning, rinse thoroughly with fresh water not to remain a chemical residue.



[↑] Cleaning-in-place (CIP) Unit...A simple mobile CIP unit with caster wheels, and CIP cleaning for plate heat exchangers without disassembly.

4— Introduction of Maintenance Services

"Full Service Package"

The "Full Service Package" is a service that is provided as a full course menu for maintenance of the plate heat exchanger. The plate heat exchanger in the plant is returned us as is, and we perform all maintenance work including disassembly, inspection, cleaning, regasketing assembly, and inspection. When completed, the unit is returned to the customer.






After completion of "Full Service package", the certified sticker is put on the unit. Records of maintenance and replaced parts are registered in the Hisaka database, and will be utilized in future maintenance.



1 Before work/after work

Flowchart of "Full Service package"








Other services

Plate cleaning...The plate cleaning work, which is the main part of the "Full Service Package", is provided as a stand-alone service.

Maintenance service on site...A service engineer visits to support maintenance work on site.



1 Maintenance service on site



5—Fault Detection

Faults occurring in plate heat exchangers are scaling, marine growth due to usage of seawater, corrosion of plates, fatigue cracking of plates, and plate deformation. Typical examples are introduced here, along with the optimum action to correct for each case.

5-1 Scaling

There are a lot of applications for plate heat exchangers, and various types of scaling will be occurred on the plate surfaces. Here, the scaling by industrial water and scaling seawater are explained.

Langelier saturation index and scaling

There is water that accelerates corrosion of piping and equipment, and those that deposit calcium carbonate to form scale. To avoid the corrosion and scaling, it is necessary to have a balanced carbonate condition as in the following equation.

$CaCO_3+CO_2+H_2O \Leftrightarrow Ca(HCO_3)_2$

In methods for applying carbonate balance in water treatment, the study published by Langelier of the United States in 1936 is well known. He devised a graph for calculating the saturation pH (pHs) for water at equilibrium, and proposed the saturation index for determining corrosions or scale tendencies.

Later, other researchers added corrections to the calculations of Langelier, and this table for deriving the saturation index has been used in Japan since the latter half of the 1950's.

How to derive the saturation index (SI)

pHs (saturation pH) = (9.3+A+B) - (C+D)

- A: Evaporation residue index
- **B:** Temperature index
- C: Calcium hardness index
- D: Alkali level

* The index of A, B, C, and D are derived from the analysis values of the water, and the following conversion table.

SI = pH (actual pH of the water) - pHs (saturated pH)

If SI > 0, scaling If SI < 0, corrosion accelerating If SI = 0, no corrosion, no scaling tendency

Most water in Japan is indicate SI < 0, and have corrosion accelerating tendency. To improve this tendency, "calcium hydroxide injection" and "calcium hydroxide/carbon dioxide gas injection" are well known.





Evaporation residue	Α	Calcium hardness	С	Alkali level	D
mg/l		mgCaCO ³ /I		mgCaCO³/l	
50 ~ 300	0.1	10 ~ 11	0.6	10 ~ 11	1.0
400 ~ 1000	0.2	12 ~ 13	0.7	12 ~ 13	1.1
		14 ~ 17	0.8	14 ~ 17	1.2
Temperature [°] C	В	18 ~ 22	0.9	18 ~ 22	1.3
0 ~ 1	2.6	23 ~ 27	1.0	23 ~ 27	1.4
2~6	2.5	28 ~ 34	1.1	28 ~ 35	1.5
7~9	2.4	35 ~ 43	1.2	36 ~ 44	1.6
10 ~ 13	2.3	44 ~ 55	1.3	45 ~ 55	1.7
14 ~ 17	2.2	56 ~ 69	1.4	56 ~ 69	1.8
18 ~ 21	2.1	70 ~ 87	1.5	70 ~ 88	1.9
22 ~ 27	2.0	88 ~ 110	1.6	89 ~ 110	2.0
28 ~ 31	1.9	111 ~ 138	1.7	111 ~ 139	2.1
32 ~ 37	1.8	139 ~ 174	1.8	140 ~ 176	2.2
38 ~ 43	1.7	175 ~ 220	1.9	177 ~ 220	2.3
44 ~ 50	1.6	230 ~ 270	2.0	230 ~ 270	2.4
51 ~ 56	1.5	280 ~ 340	2.1	280 ~ 350	2.5
57 ~ 63	1.4	350 ~ 430	2.2	360 ~ 440	2.6
64 ~ 71	1.3	440 ~ 550	2.3	450 ~ 550	2.7
72 ~ 81	1.2	560 ~ 690	2.4	560 ~ 690	2.8
		700 ~ 870	2.5	700 ~ 880	2.9
		880 ~ 1000	2.6	890 ~ 1000	3.0


Index table for A, B, C, D

5—Faults detection

Marine growth

When using seawater as the cooling fluid, slime, wood chip/fiber, seaweeds and other ocean life can clog to the port holes and accumurate on the heat transfer plates, decreasing seawater flow rate and heat transfer performance.

Because of this, many plants periodically perform disassembly cleaning (generally once a year), but this is time consuming and costly. Therefore, as an anti-fouling system, HISAKA recommends using a combination with "Hot water circulation" system in which hot water is circulated for a certain amount of time, and "Air bubbling" in which compressed air is blown through the heat exchanger.








1 Heat exchanger Seawater inlet port hole Wood chips, seaweeds and shellfish are blocking the flow channel, and causing poor flow in the unit.



Plate heat transfer surface Slim and ocean life have accumulated, and is causing poor heat transfer.







Commercial facility Y, K Company



Power plant I, D Company

5—Fault Detection

Seawater strainer

Objectives...Foreign objects such as seaweeds, shellfish, wood chip/fiber, etc. in seawater are removed so that they do not enter the plate heat exchanger, and prevents the clogging of the inlet port hole.

Operation principles...By switching the flow direction inside the filter (strainer) element, foreign objects are discharged from the backflushing valve.

Feature...(1) Backflusing is automatically performed with a pressure differential gauge and timer setting.

(2) The amount of water in the backflushing is 10% of normal flow, and cleaning is possible during operation.

(3) Because a cylindrical punched metal is used, the straining area is large.

(4) Maintenance of the punching metal part can be performed without disconnecting the main piping.

Backflusing of the strainer

Normal operation period...V1 full open/V2 full closed condition

The foreign objects flowing in from the seawater inlet nozzle is removed at the strainer zone, and strained seawater flow through the seawater outlet to the heat exchanger.

Backflushing operation period...V1 full closed/V2 full open condition


With the pressure differential gauge or timer, by closing V1 and opening V2, the seawater stream direction is forcing to change from outside of strainer zone to inside, at the time the strainer zone is backflushed and a part of seawater is discharged with foreign objects from V2.

Normal operation period...V1 full open/V2 full closed condition

The system will return to normal operation by the timer (backflushing time: approximately 10 seconds). At the time, the foreign objects in the inside of the strainer zone are moved to the backward of strainer.



Backflushing of the strainer



Model	Mesh size (mm)
EX-11	2.8 or less
EX-15	2.9 or less
UX-005	1.4 or less
UX-01	1.8 or less
UX-10	1.5 or less
UX-30	1.8 or less
UX-40	2.5 or less
UX-90	3.1 or less
UX-100,130	3.1 or less
LX-00	2.5 or less
LX-10	2.9 or less
LX-30	3.3 or less
LX-50	3.3 or less

Recommendation of strainer mesh size

Model	Mesh size (mm)
RX-00	1.8 or less
RX-30	2.1 or less
RX-13	1.9 or less
RX-70	2.9 or less
RX-90	2.6 or less
SX-41	1.7 or less
SX-43	1.1 or less
SX-70	1.6 or less
SX-90,90S,90M,90L	2.4 or less
WX-50	2.5 or less
WX-90	3.1 or less
FX-01	1.8 or less
FX-03	2.7 or less
FX-05	2.7 or less
YX-80A/B	1.7/2.0 or less

Inner strainer

This is an inner strainer made of punched metal with mesh diameter of 2-3mm. This is inserted in the inlet port of the plate heat exchanger, to remove foreign objects and debris in the fluid.



5-2 Corrosion of Plate

Corrosion is a condition where the metal is chemically or electrochemically invaded due to the surrounding environment. The plates of the plate heat exchanger use anticorrosive materials such as austenite type stainless steel and titanium, but corrosion may still occur depending on the operating conditions.

In this section, examples of past experiences in plate heat exchangers are shown, to describe action and correction on operation.

General corrosion

Anti corrosion metals such as stainless steel have a stable oxide film on the surface, called a passive film. In the case of stainless steel, a compound called hydroxide chrome forms a even, thin chemically stable film to maintain anti corrosion characteristics. In an general corrosion, corrosion progresses without this passive film forming, and the corrosion progresses across the entire surface evenly, so the surface loses its metallic gloss, and a rough surface is observed.

<Example>

- Operating time...Approx. 8 years
- Plate material...SUS316 (Stainless Steel 316)
- Duty...Chromium acid plating fluid/ cooling water
- Operating temperature...30°C
- Cause...Plate material is less corrosion resistance.
- Action and correction...After 8 years operation without fault, and is still possible to operate. But, it is necessary to increase the plate thickness, or change the material to titanium which is fully corrosion resistant, etc. A guideline of corrosion rate for material selection should be less than 0.1 mm/y.



I Magnified of the port hole of plating fluid side



1 Port hole of plating fluid side




Pitting corrosion

This is a typical localized corrosion in stainless steel. Under conditions where halogen ions (mainly Cl⁻) that destroy the passive film on the metal surface exist, dotted corrosion is observed. In the pit, metal ions dissolve out as atoms, and Cl⁻ in the fluid concentrates. Furthermore, hydrolysis of metal ions occurs, making the hydrochloric acidic condition in the pit and progresses the corrosion further.


<Example 1>

- Operating time...Approx. 1 year
- Plate material...SUS304 (Stainless Steel 304)
- Duty...Engine circulation cooling water/ cooling water
- Operating temperature...90°C
- Cause...The Cl⁻ ion concentration in the circulating fluid was 50ppm which is not a concentration that would be corroded, but localized concentration of Cl⁻ between deposit of scale and plate surface causes pitting corrosion.
- Action and correction...It is necessary to grade up the steel grade to SUS316, etc., with increased Cr, and Mo added. Also, periodic disassembly inspection and regeneration of the passive film through scale removal, and water quality control for the fluid, are recommended.



Magnified of the corroded area





5—Fault Detection

<Example 2>

- Operating time...Approx. 5 years
- Plate material...SUS304 (Stainless Steel 304)
- Duty...Steam / city water
- Operating temperature...140°C
- Phenomenon...A tiny leak from the shoulder area of the plate on the steam side by deterioration of the gasket entered the double seal area of the plate, and with the concentration of Cl⁻ ions which are factors of corrosion, corrosion attacks penetrated the plate. Consequently, the city water leaked from the double seal area of plate.
- Cause...This is a pitting corrosion due to concentration of Cl⁻ ions, caused by leaving the tiny leakage from the steam side.
- Action and correction...Replace the gasket periodically, and change to higher grade plate material like SUS316, etc.



Steam side



Stress cracking (later noted) also occurred under rust deposit



Penetration cracking in red areas (the developing fluid by DPT)





Crevice corrosion


This is another typical corrosion as pitting corrosion found in stainless steel, and is fequently occurring in plate heat exchangers. This is a type of corrosion occurs at gaps formed due to the structure, or narrow gaps between gasket seal surface and plate, and at gaps between sediments, and the mechanism is similar to pitting corrosion. Because the environment at gaps tend to be lacking in dissolved oxygen, the passive film is destroyed over time, and corrosion progresses.

<Example>


- Operating time...Approx. 6 months
- Plate material...Carpenter20 equivalent (High nickel Alloy)
- Duty...98% sulfuric acid / circulating cooling water
- Operating temperature...60°C
- Cause...It was found that the crevice corrosion is occurred by high concentration of Cl⁻ ions at the tiny gap between the cooling water side gasket and plate. Also in this case, as the crevice corrosion penetrated through the plate, 98% H₂SO₄ and cooling water were mixed and changed to the dilute sulfuric acid.

Consequently, dilute acid made general corrosion collaterally.

Action and correction...It is necessary to change the plate material to HastelloyC equivalent, and improve control to prevent concentrating the Cl⁻ ion concentration in the cooling water.




Cooling water side



1 Magnified of the cooling water side

5—Fault Detection



Crevice corrosion resistance of stainless steel

The main factor of crevice corrosion and pitting corrosion in austenite stainless steel, is the concentration of CP (chlorine ions) in water. If the CP concentration in the fluid is known, please refer to this curve to select the material.

Example) For cooling water where the CI⁻ Ion concentration is 100ppm or less, and the maximum temperature is 40°C.

There would be a slight concern for risk of corrosion with SUS304, so SUS316 is preferable.



Erosion corrosion

When the metal surface is eroded due to continuous collision of slurry, etc. in the fluid and that area becomes deeply intruded, this is called erosion corrosion. Typically this frequently occurs at narrowing or bending sections of a pipe, where the fluid velocity increases locally. Its progress depends on the type of metal or fluid, temperature, and the flow conditions of the fluid.

<Example>

- Operating time...Approx. 4 years
- Plate material...TP270 (Ti) (Stainless Steel 304)
- Duty...20% NaOH / industrial water
- Operating temperature...30°C
- Phenomenon...A severe general corrosion, penetrating pit and fluid leaks were found at the wet surface of 20% NaOH side.
- Cause...Deep erosion corrosion was found around the plate to plate contact points and part, and it was judged that erosion corrosion had progressed.
- Action and correction...Decreasing of the fluid velocity by increasing the number of plates, and removal of the slurry, and in addition, using the thicker plate is recommended. It is also necessary to check the corrosion resistance of the plate material.



T Decreasing the plate thickness due to severe erosion corrosion



Terosion corrosion at the plate contact points and near contact points




5—Fault Detection

Stress corrosion cracking

In the case that tensile stress exists in the material, stress corrosion cracking is occurred from corrosion part. In the part being existing tensile stress, destruction of the passive film, movement of atoms and voids are more likely to occur, and when that area is exposed to a corrosive environment, corrosion will especially progress in this area. The corrosion will then accelerate due to the stress, and lead to cracks.

<Example 1>

- Operating time...Approx. 2 years
- Plate material...SUS304 (Stainless Steel 304)
- Duty...Primary water / secondary water
- Operating temperature ... 90°C
- Phenomenon...There was an occurrence of rust deposit on the back side of the gasket, and a crack occurred at the gasket seal line.
- Cause...It is possible that when chloride ions in the fluid was exposed to high temperature conditions, it was concentrated at gasket areas where the flow rate is slow, and the plate was corroded here rapidly. The crack can be determined to be stress corrosion cracking due to the rust deposit occurrence and branch shape crack.
- Action and correction...Because the plate surfaces are also corroded, using SUS304 may be corroded by this water quality. We recommend to use the material to the molybdenum added SUS316, which is anti-chloride material.



Plate



 Cracking at the gasket groove



<Example 2>

- Operating time...Approx. 3 years and 7 months
- Plate material...TP270 (Titanium 270)
- Duty...Mixed organic vapors / ethylene glycol solution
- Operating temperature...99°C
- Phenomenon...A crack occurred on the plate, and leakage was found.
- Cause...Used as a condenser for mixed organic vapors (toluene, methanol, acetone, etc.). It is supposed that a crack occurred due to the methanol in the vapors, and stress corrosion cracking occurred.
- Action and correction...Austenite type stainless steel is suited for methanol existing circumstance. We recommend changing material to the type to SUS316.



1 Magnified of the vapor side



Vapor side

5—Fault Detection

5-3 Other fault detections

Fatigue crack

A condition where damage occurs from repeated stress on a material. Even low loads that would normally not be damaged can cause localized plastic deformation (deformation that will not return to the original form even when the external force is removed), and small cracks can progress to cause major damage.

<Example>

- Operating time...Approx. 13 years and 8 months
- Plate material...SUS316 (Stainless Steel 316)
- Duty...Steam / thermo oil
- Operating temperature...130°C
- Phenomenon...When brine instead of steam and thermo oil was periodically used through the unit alternatingly, a intermixing of brine and thermo oil occurred. In the 5 plates, a crack was found near the end of the center of the heat transfer zone, at lower part of the plate.
- Cause...Because there are no traces of corrosion on the plates, and the position of the cracks of each plate is the same, and because this is a position where stress will concentrate and the load is high, fatigue crack is concluded to be the cause.
- Action and correction...It is concluded that fatigue crack occurred because this unit was used for long years. To increase the strength of the plates, a thicker plate is recommended.



Magnified of the fatigue crack

Steam side (left) Thermo oil side (right)



Plate deformation


Main causes of plate deformation is due to excessive tightening, gasket expansion, etc., but there are also cases in which it occurs from water hammering. Water hammering occurs when water flow in a pipe is suddenly shut off, the momentum of flow makes a shock and vibrational water pressure through the pipe. In a plate heat exchanger, this occurs when pump startup and stop, valve opening/closing occurs too fast. This can cause severe problems, deforming the gasket grooves or contact points on the plate surfaces, etc.



<Example>

- Operating time...Approx. 13 years and 4 months
- Plate material...SUS316 (Stainless Steel 316)
- Duty...0.2MPaG steam / hot water
- Operating temperature...170°C
- Phenomenon...Deformation was found at the gasket groove of the plate on the hot water side.
- Cause...Because no corrosion or stress concentrations can be seen, water hammering made this damage.
- Action and correction...In this condition, the gasket cannot be compressed by plate deformation, and sealing is not possible. The plates were damaged, so all plates were replaced. It is necessary to improve the operating condition, to avoid water hammering.

Port hole (from the back side of the plate) can be seen to be severely deformed.



It can be seen that the double seal area (from the back side of the plate) is hollowed.

6— Overhauling

In order to extend the lifetime of the plate heat exchanger, it is important to watch changes in conditions. Frequently observed faults and causes are summarized below. If those faults are detected, please contact us and inform manufacturing number of the unit.

Faults	Decreasing of performance	• Heat transfer performance It is necessary to clean the plates and remove scale, because of supposing scaling on the heat transfer surface.
		Plow performance
		Clogging of the port holes inlet and/or scale deposition on the heat transfer surfaces may be supposed. It is necessary to clean the unit and remove scale.
	Leakage of fluids	8 From plate pack
	 Intermixing of two media 	Insufficient tightening the plate pack, damage or deterioration of gaskets, plate gasket groove or double seal area corrosion, wrong plate ar- rangement, foreign object caught between gas- ket seal surfaces, gasket twisting or overlap- ping from the groove may be the supposed. Correct each fault or replace gaskets and/or plate.
		— 4 From the S-frame
It is possi sion or d intermedi penetrate		The D-plate gasket, rubber boots, D-plate or S-
	It is possible that corro- sion or damage to the intermediate plate has penetrated the plate.	nozzle may be damaged. Replace the dam- aged part.
	Replace the damaged	5 From the E-frame
	plate.	The E-nozzle gasket, E-nozzle, rubber boots, or E-plate may be damaged. Replace the damaged part.

7— To Extend the Lifetime of Your Heat Exchanger

The ease of maintenance is one of the major benefits of the plate heat exchanger. It is possible to open the unit by just removing the tightening bolts, and the plates can be inspected visually. However, finding small corrosions and pinholes, and thoroughly cleaning tough scaling without damaging the thin plates require experienced skill.

As a technical supporter providing "relief" and "reliability" in maintenance service, we will work to help extend the life of the plate heat exchanger as long as possible. Please utilize our services for your maintenance.

Detailed information regarding maintenance is also available on our homepage. www.hisaka-asia.com



† General information regarding maintenance services with the "Full Service Package"



T Frequently asked questions and Q&A are available. Instruction manuals available for download.







Company No. 671059+K (South East Asia Headquarters) No 2, Jalan TP 2, Taman Perindustrian SIME UEP, 47600 Subang Jaya, Selangor Darul Ehsan, Malaysia Tel : +603 5880 4185 Fax : +603 8081 7185 Email : heatexc@hisala-asia.com

HISAKA WORKS, LTD

KONOIKE PLANT

2-1-48, Higashi-konoike-cho, Higashi-Osaka, Osaka, 578-0973, Japan Tel : +81 72 966 9601 Fax : +81 72 966 8923

токуо

Kyobashi Om Bldg., 1-19-8, Kyobashi Chuo-Ku, Tokyo, 104-0031, Japan Tel : +81 3 5250 0750 Fax : +81 3 3362 2759

HISAKAWORKS THAILAND CO., LTD

BANGKOK

Phairojkijja Tower, 15th Floor Zone C, 825 Bangna-Trad Road, Kwang Bangna, Khet Bangna, Bangkok 10260 Tel : +66 2744 3287 Fax : +66 2744 3286 Email : heatexc@hisaka-thai.com

RAYONG

Eastiny Park 5 Village, 222/36, Moo 10 T. Bangsarey A. Sattahip, Chonbouri Province, 20250 Tel : +66 3811 0759 Fax : +66 3811 0796 Email : heatexc@hisaka-thai.com

HISAKAWORKS SINGAPORE PTE LTD (Sales Office)

No. 18, Boon Lay Way, #02-118 Trade Hub 21 Singapore 609966

- Tel : +65 6897 8489
- Fax : +65 6686 4579
- Email : heatexc@hisaka-sing.com

PT HISAKA WORKS INDONESIA

Ruko Puri Botanical, Jl. Raya Joglo, Blok I 10 No 29, Kebun Jeruk, Jakarta Barat 11640, Indonesia

- Tel : +62 51 5890 0090
- Fax : +62 51 5890 0091
- Email : hisakindo@hisaka-asia.com

HISAVINA (Vietnam Representative Office) HO CHI MINH CITY

Hoang Dan Building, 47-49, Hoang Sa Street, Da Kao Ward, District 1, Ho Chi Minh City, Vietnam Tel : +84 8 3910 7355 Fax : +84 8 3910 7356 Email : hisavina@hisaka-asia.com

HANOI

8th Floor, Sannam Building, 78 Duy Tan St., Dich Vong Hau Ward, Cau Giay Disty., Hanoi Tel : +84 4 3975 9900 Fax : +84 4 3975 9911 Email : hisavina@hisaka-asia.com

HISAPINO (Philippines Representative Office)

One Global Place, 20th Floor, Office Business Center, 25th Street & 5th Avenue, Bonifacio Global City, Taguig 1632, Philippines Tel : +63 2224 4129 Fax : +63 2224 4130 Email : hisapino@hisaka-asia.com